

Subject: Niagara Falls Wastewater Treatment Plant Upgrade

Report to: Public Works Committee

Report date: Tuesday, September 25, 2018

Recommendations

1. That Report PW 45-2018 **BE RECEIVED** for information.

Key Facts

- Special Reference
 - Given Section 275 of the *Municipal Act, 2001*, and Regional Council's delegated authority to the Chief Administrative Officer via report GM 8-2018, that the Chief Administrative Officer consider and authorize:
 - That this report will incur expenditures or liability which exceeds \$50,000; and
 - That staff proceed with the single source award to Environmental Infrastructure Services Inc. (EIS) in the amount of \$820,785 (excluding contingency and HST) in accordance with Purchasing Bylaw 2016-02 Section 18(a)(iv) as urgency exists due to an MECP Provincial Official Order issued on July 26, 2018 for the assessment and enhanced conceptual design of the upgrades to: (1) the secondary treatment (replacement aeration) system, and (2) the anaerobic digestion system at the existing Niagara Falls Wastewater Treatment Plant (WWTP).
 - Should the Chief Administrative Officer incur an expenditure or liability greater than \$50,000, then the CAO will report to the new Council all taken pursuant to this decision.
- The purpose of this report is to provide an update on the status of the Niagara Falls WWTP secondary treatment and digestion systems and to seek approval for the single source to Environmental Infrastructure Services Inc. (EIS) for the assessment and enhanced conceptual design in order to expedite detailed design and construction to meet the conditions set by the Ministry of Environment, Conservation and Parks (MECP).
- In the recent years, there has been a number of Environmental Compliance Approval (ECA) non-compliances related to CBOD, TSS, TP, and E. coli in the Niagara Falls WWTP effluent discharge (compliance and objective limit exceedances).
- MECP issued a Provincial Official Order dated July 26, 2018 with a number of requirements including a requirement for the submission of an ECA Amendment for

the secondary treatment system to the MECP by January 2, 2020. This will require a minimum of 90% complete detailed design.

- Before initiating full detailed design of the new aeration system as well as the anaerobic digestion system, preliminary steps including condition assessments, process review, mass balances, design basis, and enhanced predesign will need to be completed immediately on a priority basis.
- The anticipated schedule for the future stages of design is: 2018 (predesign), 2019 (detailed design), and 2020 (construction).

Financial Considerations

Project 10SW1517 (Niagara Falls WWTP Upgrade) has a previously approved capital budget of \$2,100,000. To date a total of \$76,877 of funds have been spent or committed, leaving an uncommitted amount of \$2,023,123 available. Therefore sufficient budget is available to accommodate this award.

Construction funds will be requested through future the capital budget process in future years.

Analysis

The Niagara Falls WWTP is owned and operated by Niagara Region. The Plant was originally constructed in 1963 and has been upgraded periodically since then with the main upgrades occurring in 1982 (plant expansion), and 1986 (conversion to secondary treatment). It is located at the intersection of Stanley Avenue and Swayze Drive in the City of Niagara Falls. The existing sewer infrastructure consists of storm, sanitary, and combined sewers, and 20 sewage pumping stations (SPS). The sanitary and combined sewers discharge to the Niagara Falls WWTP. The service area covers approximately 60 square kilometres.

The existing service population consists of approximately 80,000 year-round residents; however, Niagara Falls experiences seasonal changes in population due to visiting tourists. It is estimated that Niagara Falls hosts approximately 14 million tourists per year, primarily between the months of May and September.

Under normal operating conditions, the Niagara Falls WWTP provides treatment via screening, grit removal, primary clarification, rotating biological contactors (RBC): total of 35 (5 trains of 7) contactor units for biological treatment, secondary clarifiers, and disinfection via chlorination/dechlorination. Ferric chloride is added for chemical phosphorus removal. A polymer feed system is available to provide chemically enhanced primary treatment (CEPT).

Figure 1 in Appendix 2 presents a process flow diagram (PFD) of the Niagara Falls WWTP liquid treatment and solids management trains, and Figure 2 presents an aerial image of the Niagara Falls WWTP site.

The rated average day flow (ADF) capacity of the Niagara Falls WWTP is 68,300 m³/d. The Plant is also rated for a peak dry weather flow rate of 136,400 m³/d and a peak wet weather flow rate of 205,000 m³/d.

Waste sludge is stabilized by two-stage anaerobic digestion, and the resulting biosolids are dewatered on-site. Waste sludge from the Queenston WWTP is also hauled to the Niagara Falls WWTP for stabilization and dewatering. The dewatered cake is disposed off-site.

Treated effluent is discharged to the Queenston Power Canal.

The existing facility is old and has experienced operational difficulties, including failures of the RBC shafts, bearings, gearboxes, and turnbuckles. In addition, significant sulfide loading to the RBC system has resulted in growth of hydrogen sulfide oxidizing bacteria on the RBC media and mechanical equipment failures. The RBCs have historically operated within typical organic loading values, however, increases in influent flow and loadings could result in decreased BOD removal and development of anaerobic conditions in the first stage RBCs, which would favour the growth of nuisance organisms.

To date, there have been a number of ECA non-compliances related to CBOD, TSS, TP, and E. coli in the effluent (compliance and objective limit exceedances).

Previous studies were completed in 2014 and 2017 by XCG Consultants (now Cole Engineering Group) to review options for the secondary treatment system. Upon further review, additional information related to asset condition, process optimization and design scoping is required to progress the secondary treatment and digestion systems into detailed design and ultimately construction. Additionally, the 2016 MSP identified a new WWTP in south Niagara Falls that will impact the flows to the existing WWTP, which requires further review and confirmation of existing and future flows for process optimization and design.

In addition to the secondary biological system (new aeration system to replace RBCs) and aging infrastructure related deficiencies described above, the plant has experienced anaerobic digester failures in the recent years (2014 and 2017).

MECP issued a Provincial Official Order dated July 26, 2018 with a number of requirements including a requirement for the submission of an ECA Amendment for the secondary treatment system to the MECP by January 2, 2020. The Order creates urgency in completing this complex design for the secondary treatment.

Given the magnitude and intricacies associated with the scope of work, staff recommend a phased approach to design – Phase 1) Assessment and Enhanced Conceptual Design Phase 2) Detailed Design. Fully understanding the condition and operation of the WWTP will facilitate a seamless transition into Phase 2 (detailed design) and aims to eliminate ambiguity and increase accuracy in scope, costing and understanding of risks. This phased-design approach is utilized by other municipalities in Southern Ontario on large scale facility upgrades. The Region will also be implementing this on the Anger Avenue Wastewater Treatment Plant upgrade project (2000695) using a competitive procurement model, via a Request for Proposals call from prequalified consultants (using 2017-RFPQ-03).

Liquid (i.e., secondary treatment) and solids (digestion) treatment trains are included in Phase 1 of the scope of the work as it allows for a holistic view of the interconnected WWTP operations. Also, in addition to the issued Order, MECP is monitoring and aware of the digester issues that NFWWTP has experienced. Phase 2 scope can be developed and detailed design for the liquid and solids treatment trains can then be separated, if necessary. Controls will be put into place to ensure that one portion of the project is not holding up another, especially for secondary treatment.

The Project team has worked collaboratively to develop the following comprehensive scope required to successfully complete Phase 1:

Conduct condition assessments and reporting for the following:

- Existing secondary clarifiers and gallery
- Existing primary clarifiers (1, 2, and 3) and chlorine contact tank
- Existing secondary digester (Digester 4) and gallery
- Existing main power substation and standby power

Conduct individual studies and develop tech memos as follows:

- Design basis and mass balance
- New aeration system
- Secondary clarifier and RAS/WAS pumping
- Chlorination and dechlorination tank
- Upgrades of aeration system for existing aerated grit system and primary effluent channels
- Hydraulic profile
- Feasibility to relocate existing ferric system and provide flexibility for alternative chemicals
- Feasibility of sludge thickening to optimize sludge digestion system
- New primary digestion system
- Upgrading requirements to the existing secondary digester and biogas system
- Upgrading requirements to the main power substation and standby power

Conduct a topographic survey of the project site.

Generate Project Scoping Report (PSR)

- Compliance with all applicable acts, regulations, codes and standards
- Compliance with design standards
- Project constraints / opportunities
- Site layout
- Field investigation analysis and results summary (with reports appended)
- Confirmation and/or modification of the plant conceptual design basis and criteria
- Conceptual design and scope for wastewater treatment (liquid train)
- Conceptual design and scope for wastewater treatment (solids train)
- Conceptual design and scope for power supply and distribution
- Conceptual design and scope for Control and SCADA system
- Conceptual design and scope for site plan upgrades
- Identification of potential construction constraints
- Identification of plant operation constraints during construction
- Preliminary project schedule
- Cost estimate to +/- 20% (Class 'C' cost estimate)
- Pending significant issues to be addressed/resolved during design stage
- Conceptual design drawings
- Registers / Plans

Detailed design (Phase 2) will follow immediately after the completion of Phase 1.

Alternatives Reviewed

The anticipated schedule for the secondary treatment and digestion system upgrades is 2018 (predesign), 2019 (detailed design), and 2020 (construction). Based on projects completed of similar scope and size, phase 1 could take up to 1 year and phase 2 could take 1.5 years to 2 years to complete. To meet the requirements of the MECP Order of an ECA Amendment submission by January 2, 2020, this work will have to be significantly expedited. The following are alternatives that have been reviewed by staff:

- 1) Do nothing not a viable option considering the July 26, 2018 MECP Order and the recent ECA non-compliances reported for the Niagara Falls WWTP effluent discharge. Niagara Region can be fined by MECP if this condition is not met.
- 2) Single source (Phase 1) and single source (Phase 2) viable option but not recommended at this point. Assuming award following October 4, 2018, this option provides the maximum duration for detailed design (phase 2) to approximately one year, however, is not being recommended at this point as it does not promote formal competitive procurement at any design phase.
- 3) Formal RFP procurement (Phase 1) and formal RFP procurement (Phase 2) not a viable option as this only allows for 5 months to complete the detailed design (phase 2). Based on similar projects, this is inadequate time to complete the works.

4) Single source (Phase 1) and formal RFP procurement (Phase 2) – viable and recommended option. Assuming award following October 4, 2018 Council meeting, this option allows for approximately 5 months for phase 1 and approximately 8 months for phase 2. It also promotes formal competitive procurement in phase 2.

Staff recommend that Environmental Infrastructure Services Inc. (EIS) be awarded phase 1 in accordance with Purchasing Bylaw 2016-02 Section 18(a)(iv) as urgency exists and there is limited time to obtain services by means of an open or roster request for proposals. EIS has provided an aggressive timeline for delivery of the Project Scoping Report, which is five (5) months from award. Presuming phase 2 is awarded through formal procurement, the schedule for detailed design is anticipated to be Spring 2019 to January 2020 (approximately 8 months), which is very aggressive but necessary to satisfy the MECP's Provincial Official Order.

EIS was selected for phase 1 due to their involvement at NFWWTP during the digester failures, their extensive knowledge and staff expertise in wastewater treatment in the Region and other municipalities across Ontario, intimate knowledge of Region's design manual, and for their commitment to the Region and understanding of the significance of the current compliance issues. EIS will assign dedicated staff to this assignment for the duration to ensure consistency, quality, and timely delivery. The Region has had great success with EIS in terms of coordination, delivery, quality, and risk management. Region staff are familiar with the proposed EIS Project team having worked closely on other recent Regional projects.

EIS letter proposal, including scope, team, cost and schedule is attached for reference (Appendix 1). The total amount being recommended for single source assignment is \$820,785.00 (excluding HST and contingency).

Other Pertinent Reports

N/A

PW 45-2018 September 25, 2018 Page 7

Prepared by: Shahab Shafai, M.Sc., P.Eng. Associate Director of Wastewater Public Works Department

Recommended by: Ron Tripp, P.Eng. Commissioner Public Works Department

Submitted by: Carmelo D'Angelo, BSc, MPA Chief Administrative Officer

This report was prepared in consultation with Lisa Vespi, P.Eng. Senior Project Manager, W-WW Engineering and Michael Leckey, Program Financial Specialist W-WW and reviewed by Joe Tonellato, Director W-WW Services.

Appendices

Appendix 1EIS Letter ProposalAppendix 2Process Flow Diagram Niagara Falls Wastewater Treatment Plant



ENVIRONMENTAL INFRASTRUCTURE SOLUTIONS INC.

August 20th, 2018 Our Ref: PEE18-103

via: Email

Ms. Lisa Vespi, P.Eng. Senior Project Manager Water & Wastewater Services Regional Municipality of Niagara 3501 Schmon Parkway P.O. Box 1042 Thorold, ON L2V 4T7

Dear Ms. Vespi:

Re: Niagara Falls Wastewater Treatment Plant (NFWWTP) Secondary Treatment and Digestion System Project Scoping and Conceptual Design

Environmental Infrastructure Solutions Inc. (EIS) is pleased to submit a cost proposal for the scope of work related to NFWWTP Secondary Treatment and Digestion System Project Scoping and Conceptual Design. Our understanding of the scope of work is in line with the terms of reference provided by the Region and outlined below:

- Conduct condition assessments and reporting for the following:
 - Existing secondary clarifiers and gallery:
 - Estimate remaining service life for main structure of tanks;
 - Recommend upgrades to existing structures and all components to allow future operation for a minimum of 20 years;
 - Conduct risk evaluation for structural modifications to the existing clarifiers to suit the requirements of hydraulic capacity increase and new RAS system and provide recommendations;
 - Existing primary clarifiers (1,2 and 3) and chlorine contact tank
 - Existing secondary digester (Digester #4) and gallery
 - Estimate remaining service life for major components;
 - Verify and identify actual capacities for each major component;
 - Recommend upgrades to suit new demand;
 - o Existing main power substation and standby power
 - Estimate remaining service life for main structure and roof;
 - Recommend upgrades if required.



- Conduct Individual Studies and Tech Memos as follows:
 - Design basis and Mass balance
 - Review and verify plant influent loadings;
 - Review and verify secondary influent loadings and required treatment efficiency;
 - Compute and define material/media that will be released or discharged to the environment and solids train;
 - Compute and define design criteria for demand of chemicals;
 - New aeration system
 - Aeration tanks;
 - Air blower system;
 - Secondary clarifier and RAS/WAS pumping
 - Upgrade of existing secondary clarifier and/or new tankage requirement;
 - RAS/WAS pumping system;
 - Chlorination and dechlorination tank
 - Upgrades of aeration system for existing aerated grit system and primary effluent channels
 - o Hydraulic profile
 - Maximum available heads and capacities of existing facility and each unit process;
 - Proposed revised water levels according to required hydraulic capacities for each unit process;
 - Required flow measurements and plant effluent flow monitoring to meet ECA requirements;
 - Feasibility to relocate existing ferric system and provide flexibility for alternative chemicals
 - o Feasibility of sludge thickening to optimize sludge digestion system
 - New primary digestion system
 - Primary digester;
 - Control building;
 - o Upgrading requirements to the existing secondary digester and biogas system
 - Secondary digestion and piping system;
 - Biogas handling/storage;
 - Existing waste gas burner (WGB) system;
 - o Upgrading requirements to the main power substation and standby power



- Generate Project Scoping Report (PSR)
 - The PSR shall include the following and must be in place prior to the Region proceeding with the design RFP:
 - Compliance with all applicable acts, regulations, codes and standards;
 - Compliance with design standards (i.e. Project Design Manual, Niagara SCADA Standards, Niagara Peninsula Standard Contract Document, Niagara Peninsula CAD Standards, etc.)
 - Project constraints / opportunities;
 - Site layout;
 - Field investigation analysis and results summary (with reports appended);
 - Confirmation and/or modification of the plant conceptual design basis and criteria as follows:
 - Plant hydraulic loading and data;
 - Influent parameter and loading;
 - Plant effluent limits and objectives;
 - Raw sludge and scum generation, WAS and scum generation (to be loaded to solids train)
 - Conceptual design and scope for wastewater treatment (liquid train);
 - Conceptual design and scope for wastewater treatment (solid train);
 - Conceptual design and scope for power supply and distribution;
 - Conceptual design and scope for Control and SCADA system;
 - Conceptual design and scope for site plan upgrades;
 - Identification of potential construction constraints;
 - Identification of plant operation constraints during construction;
 - Preliminary project schedule;
 - Cost estimate to +/- 20% (Class 'C' cost estimate);
 - Pending significant issues to be addressed/resolved during design stage;
 - Conceptual design drawings;
 - Registers / Plans.
- Conduct a topographic survey of the project site in accordance with ASCE 38-02 quality level D and C. At a minimum the survey shall identify the location of all surface and underground features and shall include but not be limited to:
 - Property boundaries including identifiable properties bars or markers;
 - Roadway and driveway limits including surface classification, sidewalks, curb & gutter, roadway centerline, edge of pavement, shoulders, etc.;



- o Limits of structures and/or buildings including finished floor elevations;
- o Limits and types of fencing and gates;
- Location of above ground/below ground utilities and their appurtenances (i.e. poles and guy wires, pedestals, vaults, manholes, electrical boxes, valve boxes, meters, gas regulators, traffic signals, etc.);
- Location of buried infrastructure (i.e. watermain, storm sewer, sanitary sewer including valve boxes, manholes, catch basins, hydrants, valve chambers, drain chambers, air release chambers, curb stops, clean outs, ditch inlets, etc.)
- Size, type and invert elevations of all sewers;
- Elevations of all buried infrastructure are to be verified in the field (i.e. Invert elevations of sewers, top of nut elevation on valves, top of watermain and/or forcemain in chambers, etc.);
- o Location, diameter and dripline of all trees and shrubs and flower beds;
- o All street signs complete with description;
- Limits of ditches and natural watercourses including top of bank and ditch inverts and size and type of all culverts and headwalls; and
- Any and all surface features that may have an impact or be disturbed during construction within the project boundary.

Project Schedule

Since we understand the urgency of this assignment, we have put together a very aggressive schedule with a completion date of early January 2019. However, we would like to inform the Region that the condition assessments outlined above are on the critical path of our schedule and delays associated with the scheduling of these intrusive investigations may negatively impact our anticipated deliverable dates. A copy of our tentative baseline schedule has been enclosed with this letter.

Engineering Fees

Our engineering fees associated with this assignment are presented in the Engineering Fees Estimate Table enclosed with this letter.

In Closing

EIS would like to thank the Regional Municipality of Niagara for this bidding opportunity and we look forward to a positive consideration.

Should you have any questions on the submitted quote, please do not hesitate to contact the undersigned.



Yours truly,

ENVIRONMENTAL INFRASTRUCTURE SOLUTIONS INC.

Horia Ispas, P.Eng, PMP Project Manager

HI/db

Enclosures:

- 1. Baseline Project Schedule
- 2. Engineering Fees Estimate Table

Engineering Fees Estimate Table Niagara Falls WWTP Secondary Treatment and Digestion System Upgrades Project Scoping and Conceptual Design EIS Proposal No.: PEE18-103

								o /		.*								
	Star		ø	ø	S. S.	la la	101.00 10	۶ ۱	روع <i>م</i>	ia Mili							88	
	5. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	B.Eng	2. P.E.	Pead Cead	2'S F	Na '8	55. D.	10 10 S	Son Star	50 50 V	8. 00 × 00	Sort Proc		3			4 Du.	5 / ž
	Vanag, P.	Wang al Man Lead	Namiciu Cal Le	1. M.S.	dar Jo al Lea	17 D 2	aza, M. al Field	Cond Dhic S	a Sup	(1) (1) (1) (1)	1) M.E. 21,012	rtei, B.	hoor	Suppo	Sures	^{Toinee} ,	emen	^ک تخ
	oria s olicit	onnie chnic cess	rdrei A echan	Nhn Lin	et san	1 111 100		homas pooras	^{ll} al Sh	tioe W	uis De Schnice	stiri p schnic	40 Su	lenical,	otal H	otal Er	isterna a	otal Ta
Task Description	¥ ¢ /	& ~ ¢	7 4 7	84	<i>₹ 6</i> 7 / 4	x C /	そじ />	S 29	1 2 2	\ S R	~~~~~	\$ R	୍ <u>୯</u>	/ 0°	~ (/ ~	/ Q	
Place of Employment:	EIS	EIS	EIS	EIS	EIS	EIS	BME	Lejan	EIS	EIS	EIS	EIS	EIS	EIS				
Hourly Rate (\$):	\$140	\$140	\$120	\$130	\$130	\$120	LS	LS	\$120	\$90	\$90	\$90	\$80	\$60				
															150.0	A 00 700 00		A 04 705 00
Project Meetings and Teleconferences (Allowed for 10 x 4 Hrs. Biweekly Meetings and 10 x 2 Hrs. Teleconferences)	60.0	60.0		30.0											150.0	\$ 20,700.00	\$ 1,035.00	\$ 21,735.00
Uraft Project Scoping Report Workshop (Allowed for full day 8 Hrs. Workshop)	8.0	8.0		8.0											24.0	\$ 3,280.00	\$ 164.00	\$ 3,444.00
Project Management and Reporting Total Hours:	68.0	68.0	0.0	38.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	174.0	• •• •• •• ••		
Project Management and Reporting Total Fees:	\$ 9,520.00	§ 9,520.00 §	i - Ş	4,940.00 \$	5 - \$	- :	\$ - \$	-	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		\$ 23,980.00	\$ 1,199.00	\$ 25,179.00
CONDITION ASSESSMENTS AND REPORTING					10.0						10.0			(0.0		A (0.000.00		.
Existing Secondary Clarifiers and Gallery	8.0	24.0			16.0				40.0		40.0			16.0	144.0	\$ 40,920.00	\$ 2,046.00	\$ 42,966.00
Existing Primary Clarifiers (1,2 and 3)	8.0	8.0			16.0				40.0		40.0			16.0	128.0	\$ 28,680.00	\$ 1,434.00	\$ 30,114.00
Existing Chlorine Contact Tank	8.0	8.0			16.0				40.0		40.0			16.0	128.0	\$ 23,680.00	\$ 1,184.00	\$ 24,864.00
Existing Secondary Digester (Digester #4) and Gallery	8.0	8.0			16.0				40.0		40.0			16.0	128.0	\$ 33,680.00	\$ 1,684.00	\$ 35,364.00
Existing Main Power Substation and Standby Genset	8.0	24.0	80.0	80.0					40.0	80.0	80.0			16.0	408.0	\$ 44,640.00	\$ 2,232.00	\$ 46,872.00
Condition Assessments and Reporting Total Hours:	40.0	72.0	80.0	80.0	64.0	0.0	0.0	0.0	200.0	80.0	240.0	0.0	0.0	80.0	936.0			
Condition Assessments and Reporting Total Fees:	\$ 5,600.00	\$ 10,080.00 \$	\$ 9,600.00 \$	10,400.00 \$	\$ 8,320.00 \$	- 8	\$ 70,000.00 \$	-	\$ 24,000.00	\$ 7,200.00	\$ 21,600.00	\$-	\$-	\$ 4,800.00		\$ 171,600.00	\$ 8,580.00	\$ 180,180.00
SYSTEM AND PROCESS STUDIES AND REPORTING																	r	
Design Basis and Mass Balance	16.0	60.0							40.0	60.0	60.0	50.0		24.0	310.0	\$ 32,180.00	\$ 1,609.00	\$ 33,789.00
Aeration Tanks	16.0	60.0		16.0	16.0				40.0	60.0		50.0		24.0	282.0	\$ 30,940.00	<u>\$ 1,547.00</u>	\$ 32,487.00
Air Blower System	16.0	60.0	8.0	8.0	8.0				40.0	60.0		50.0		24.0	274.0	\$ 29,820.00	\$ 1,491.00	\$ 31,311.00
Secondary Clarifiers Upgrades	16.0	60.0							40.0	60.0	60.0	50.0		24.0	310.0	\$ 32,180.00	<u>\$ 1,609.00</u>	\$ 33,789.00
RAS/WAS Pumping System	16.0	40.0		8.0					40.0	60.0		50.0		24.0	238.0	\$ 25,020.00	\$ 1,251.00	\$ 26,271.00
Chlorination and Dechlorination Tank	16.0	40.0			8.0				40.0	60.0		50.0		24.0	238.0	\$ 25,020.00	\$ 1,251.00	\$ 26,271.00
Existing Aerated Grit System and Primary Effluent Channels	16.0	40.0							40.0	60.0		50.0		24.0	230.0	\$ 23,980.00	\$ 1,199.00	\$ 25,179.00
Hydraulic Profile	16.0	80.0							40.0	60.0		50.0		24.0	270.0	\$ 29,580.00	\$ 1,479.00	\$ 31,059.00
Ferric System Upgrades	16.0	60.0	8.0						40.0	60.0	60.0	50.0		24.0	318.0	\$ 33,140.00	\$ 1,657.00	\$ 34,797.00
Feasibility of Sludge Thickening for Sludge Digestion System Optimization	16.0	60.0							40.0	60.0	60.0	50.0		24.0	310.0	\$ 32,180.00	\$ 1,609.00	\$ 33,789.00
Primary Digestion System and Control Building Upgrades	16.0	40.0							40.0	60.0	60.0	50.0		24.0	290.0	\$ 29,380.00	\$ 1,469.00	\$ 30,849.00
Secondary Digestion and Piping System Upgrades	16.0	40.0			8.0				40.0		60.0	50.0		24.0	238.0	\$ 25,020.00	\$ 1,251.00	\$ 26,271.00
Biogas System (Handling/Storage and WGB) Upgrades	16.0	40.0	16.0						40.0		60.0	50.0		24.0	246.0	\$ 25,900.00	\$ 1,295.00	\$ 27,195.00
Main Power Substation and Standby Genset Upgrades	16.0	40.0	80.0	120.0	8.0				40.0		60.0	50.0		24.0	438.0	\$ 50,220.00	\$ 2,511.00	\$ 52,731.00
System and Process Studies and Reporting Total Hours:	224.0	720.0	112.0	152.0	48.0	0.0	0.0	0.0	560.0	660.0	480.0	700.0	0.0	336.0	3,992.0			
Condition Assessments and Reporting Total Fees:	\$ 31,360.00	\$ 100,800.00	5 13,440.00 \$	19,760.00 \$	\$ 6,240.00 \$	- 3	\$ - \$	-	\$ 67,200.00	\$ 59,400.00	\$ 43,200.00	\$ 63,000.00	\$-	\$ 20,160.00		\$ 424,560.00	\$ 21,228.00	\$ 445,788.00
PROJECT SCOPING AND REPORTING																		
Generate Draft Project Scoping Report	40.0	40.0	40.0	40.0	40.0	16.0			80.0	80.0	80.0	80.0		40.0	576.0	\$ 61,920.00	\$ 3,096.00	\$ 65,016.00
Generate Final Project Scoping Report	8.0	8.0	2.0	2.0	2.0	2.0			16.0					16.0	56.0	\$ 6,120.00	\$ 306.00	\$ 6,426.00
Project Scoping and Reporting Total Hours:	48.0	48.0	42.0	42.0	42.0	18.0	0.0	0.0	96.0	80.0	. 80.0	80.0	0.0	. 56.0	632.0			
Project Scoping and Reporting Total Fees:	\$ 6,720.00	§ 6,720.00	5,040.00 \$	5,460.00 \$	\$ 5,460.00 \$	2,160.00	\$-\$	-	\$ 11,520.00	\$ 7,200.00	\$ 7,200.00	\$ 7,200.00	\$-	\$ 3,360.00		\$ 68,040.00	\$ 3,402.00	\$ 71,442.00
ENHANCED CONCEPTUAL DESIGN																	r	
Generate Conceptual Design Drawings	16.0	40.0	16.0	16.0	16.0	40.0					1		500.0		644.0	\$ 58,720.00	\$ 2,936.00	\$ 61,656.00
I opograpnic Survey						40.0									40.0	\$ 34,800.00	\$ 1,740.00	\$ 36,540.00
Enhanced Conceptual Design Total Hours:	16.0	40.0	16.0	16.0	16.0	80.0	0.0	0.0	0.0	0.0	0.0	0.0	500.0	0.0	684.0			
Enhanced Conceptual Design Total Fees:	\$ 2,240.00	5,600.00	5 1,920.00 \$	2,080.00 \$	2,080.00 \$	9,600.00	\$ - \$	30,000.00	\$ -	\$ -	5 -	Ş -	\$ 40,000.00	\$ -		\$ 93,520.00	\$ 4,676.00	\$ 98,196.00
	396.0	948.0	250.0	328.0		98.0	0.0	20.000.00	\$ 102 720 90	820.0	800.0	780.0	500.0	472.0	6,418.0	¢ 791 700 00	\$ 20.095.00	\$ 920 795 00

Environmental Infrastructure Solutions Inc.

Project Schedule

Niagara Falls WWTP Secondary Treatment Scoping and Conceptual Design EIS Proposal No.: PEE18-103

ID	Task Name	Start	Finish	August Aug	September Sep	October
0	Project Summary	Mon 18-08-27	Fri 19-01-04			
1	1 Project Management	Mon 18-08-27	Fri 19-01-04			
2	1.1 Conduct Progress Meetings and Teleconferences, Submit Deliverables, other PM Duties	Mon 18-08-27	Fri 19-01-04			
3	2 Condition Assessments	Mon 18-08-27	Fri 18-09-21		0%	
4	2.1 Conduct Condition Assessment and Reporting for Existing Secondary Clarifiers and Gallery	Mon 18-08-27	Fri 18-09-21			
5	2.2 Conduct Condition Assessment and Reporting for Existing Primary Clarifiers 1, 2 and 3	Mon 18-08-27	Fri 18-09-21			-
6	2.3 Conduct Condition Assessment and Reporting for Existing Chlorine Contact Tank	Mon 18-08-27	Fri 18-09-21			-
7	2.4 Conduct Condition Assessment and Reporting for Existing Secondary Digester (Digester #4) and Gallery	Mon 18-08-27	Fri 18-09-21			-
8	2.5 Conduct Condition Assessment and Reporting for Existing Main Power Substation and Standby Genset	Mon 18-08-27	Fri 18-09-21			-
9	3 System and Process Studies and Reporting	Mon 18-09-24	Fri 18-12-21			
10	3.1 Generate and Submit Report on Design Basis and Mass Balance	Mon 18-09-24	Fri 18-10-19			0,
11	3.2 Generate and Submit Report on Aeration Tanks	Mon 18-10-08	Fri 18-11-16			
12	3.3 Generate and Submit Report on Air Blower System	Mon 18-10-15	Fri 18-11-09			
13	3.4 Generate and Submit Report on Secondary Clarifiers Upgrades	Mon 18-10-01	Fri 18-11-16			
14	3.5 Generate and Submit Report on RAS/WAS Pumping System	Mon 18-10-15	Fri 18-11-09			
15	3.6 Generate and Submit Report on Chlorination and Dechlorination Tank	Mon 18-09-24	Fri 18-10-19			0'
16	3.7 Generate and Submit Report on Existing Aerated Grit System and Primary Effluent Channels	Mon 18-09-24	Fri 18-10-19			0,
17	3.8 Generate and Submit Report on Hydraulic Profile	Mon 18-10-08	Fri 18-11-30			
18	3.9 Generate and Submit Report on Ferric System Upgrades	Mon 18-10-15	Fri 18-11-09			
19	3.10 Generate and Submit Report on Feasibility of Sludge Thickening for Sludge Digestion System Optimization	Mon 18-09-24	Fri 18-11-02			
20	3.11 Generate and Submit Report on Primary Digestion System and Control Building Upgrades	Mon 18-11-05	Fri 18-12-14			
21	3.12 Generate and Submit Report on Biogas System (Handling/Storage and WGB) Upgrades	Mon 18-11-05	Fri 18-12-07			
22	3.13 Generate and Submit Report on Main Power Substation and Standby Genset Upgrades	Mon 18-10-29	Fri 18-12-21			<u> </u>
23	4 Project Scoping and Reporting	Mon 18-11-26	Fri 19-01-04			-
24	4.1 Generate and Submit Draft Project Scoping Report	Mon 18-11-26	Fri 19-01-04			
25	5 Enhanced Conceptual Design	Mon 18-09-24	Fri 18-12-21			
26	5.1 Generate and Submit Conceptual Drawings	Mon 18-09-24	Fri 18-12-21			
			1			

	Critical	Task	Baseline		Milestone	♦	Project Summary
EIS Proposal No.: PEE18-103	Critical Split	 Split	 Baseline Split		Summary Progress		External Tasks
	Critical Progress	 Task Progress	Baseline Milestone	\diamond	Summary	\checkmark	External Milestone

Niagara Region

November December January Nov Dec Jan 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0%				
Nov Dec Jan 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0%		November	December	January
		Nov	Dec	Jan
				0%
			09	%
		<u> </u>		
0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0%		0%		
		0%		
		0%		
			0%	
		0%		
		00/		
0% 0% 0% 0% 0%		-0%		
0%			0%	
0%			0%	
0%			<u>۸۷</u>	
0%			070)
0%				0%
0%				0%
0%	_		09	%
0%				
			0%)
			0%	0% 0%
	_	De	eadline 🖓	
	_)		
Deadline ↔				
Deadline 🖓				



Figure 1: Process Flow Diagram (PFD), Niagara Falls Wastewater Treatment Plant