Project Category No.	Project Types include design and/or construction. All projects must be recommended from a Study. All projects exclude internal costs incurred on projects.	100% Funding Amount Priority	Region %	LAM %
1.	Sewer Separation	40%		
Work Examples	Disconnection of road drainage		40	60
	Disconnection of road and private		60	40
	Disconnection of road, previous disconnection of private or oposite		50	50
2.	Studies	15%		
Work Examples	PPCP as per the PPCP Guide		50	50
	I&I and extraneous flow investigation including CCTV/smoke testing ¹		50	50
	Mandatory Flow Monitoring - Pre and Post		60	40
	Investigative work on Municipal/Private side		50	50
	Public Education/Water conservation and efficiency measures		50	50
	Sewer Use By-Law development/update and Municipal Policies		50	50
3.	Source Control - Private Side	20%		
Disconnecti	on of roof leaders - prerequisite for other works on the private side.			
Work Examples	Disconnection of roof leaders		60	40
	Disconnection of weeping tiles from sanitary including applicable works		60	40
	Private property disconnection of sump pumps		60	40
	Backflow preventor installation on sanitary		40	60
4.	Conveyance and Flow control/storage	15%		
Work Examples	Real time control for detention		60	40
	In-line flow controlers design & construction (e.g. weirs)		60	40
	Off-line conveyance and pumping design and construction		60	40
	In-line / Off-line Storage		40	60
5.	Repair/ Rehabilitation/ Replacement of Sewers (estimated ≥50% flow reduction during WW events)	10%		
Work Examples	Repair of sanitary/ manholes - gel sealing, spot repairs		30	70
	Spot repair lining		30	70
	Full length liner		30	70

Note 1: CCTV inspection - only site/project specific. Regular **city wide** inspections should be part of municipal Asset Management or O&M programs.